ANNEXURE CP1.C

CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINES

Council Reference No.	
Country Notice Chick 140.	

EXAMPLE SUBDIVISIONAL INSPECTION & TEST PLAN

DEVELOPMENT NAME: Consulting Engineer:

Elements of Work	Testing Requirements			Consulting Engineer's Responsibility	Council's Responsibility
	Test	Standard * (Refer Note 1)	Frequency		
Pre-Start Meeting		Construction Procedures CP1		Outline performance and standard required.	Outline performance and standard required.
				Highlight critical aspects of the design.	Highlight critical aspects of the design.
Allotment Filling		_		Lovel 1 auponiaion to	
Quality of Material	Visual			Level 1 supervision to allotments and within road	Visit site for random audit
Compaction	AS1298	Refer AS3798	Refer AS3798	reserve, Level 2	inspections if considered
Alignment	FSL survey lot boundaries and features	J	J	Supervision elsewhere in accordance with AS3798.	warranted.
Subgrade					Visit site for random audit
Compaction	AS1289	Construction Specification C213	Construction Specification C213	Engineer to make routine visits and to attend during	inspections (including joint inspections during proof
	& Proof Rolling	No discernible movement		proof rolling and to	rolling) if considered
CBR Tests	CBR 4 day Soaked (1pt)	Construction Specification C213	Construction Specification C213	examine and assess all test results and cross	warranted.
	and in-situ CBR			section geometry.	Pavement Design approval before
Horizontal and Vertical Alignments	Survey	Construction Specification C213	IP, TP, Centreline (25m)	Pavement Design to be	proceeding with
Profile	String Line	Construction Specification C213	25m	prepared.	placement of pavement layers.

^{*} Note 1: All references relate to the Capricorn Municipal Development Guidelines

Council Reference No:	
-----------------------	--

EXAMPLE SUBDIVISIONAL INSPECTION & TEST PLAN

DEVELOPMENT NAME: Consulting Engineer:

Elements of Work	Testing Requirements		Consulting Engineer's Responsibility	Council's Responsibility	
	Test	Standard *(Refer Note 1)	Frequency		
Subgrade Replacement (CBR 15 Material)				Engineer to make sufficient routine visits to	
Material Quality	QA material supplier	Construction Specification C213		assess quality of materials	Visit site for random audit
Compaction	Proof Rolling	No discernible movement	Construction Specification	& that operations will achieve a sound	inspections if considered
(a) For on site material	Minimum Roller Passes	Visual	C213	compacted layer & to	warranted.
(b) For graded material	AS1289	98% Standard		examine & assess all test	
Profile & Depth	String Line/ Survey	25m	IJ	results	
Sub-base Layer				Facine and analysis as time	
Material	QA Material Supplier	DOT Standard Spec MRS11.05	Construction Specification	Engineer to make routine visits & to attend proof	Visit site for random inspections if considered warranted
Compaction	AS1289	100% Standard	C242	rolling & examine &	
Profile & Depth	String Line/ Survey	Construction Specification C242	J	assess all test results	
Base Layer					
Material Quality	QA Material Supplier	DOT Standard Spec MRS11.05			
	Proof Rolling	No discernible movement	Construction Specification		
Compaction	AS1289	100% Standard	C242	Engineer to make routine	Visit site for random audit inspections (including joint inspections during proof rolling) if considered
Horizontal & Vertical Alignments			J	visits & to attend proof rolling & examine &	
(i) With no Kerb & Channelling	Reduced Level	Construction Specification C242	3 per 200m	assess all test results	warranted.
(ii) With Kerb & Channelling	Reduced Level	Construction Specification C242	20m		
Profile	String Line	Construction Specification C242	20m		

^{*} Note 1: All references relate to the Capricorn Municipal Development Guidelines

Council Reference No:	
-----------------------	--

DEVELOPMENT NAME: Consulting Engineer:	
--	--

Elements of Work	Testing Requirements		Consulting Engineer's Responsibility	Council's Responsibility	
	Test	Standard *(Refer Note 1)	Frequency		
Asphalt Surfacing Material Quality Compaction and Thickness Horizontal & Vertical Alignments	QA Material Supplier AC Core Test – With Completed 'Random Sampling Location' sheet # String Line	Construction Specifications C245.	Asphalt Core Test 1 Test Per 400m2 As per C245 Horizontal - 1 Test Per 200m2 Vertical - 1 Test Per 50m	Engineer to undertake a Pre-seal Inspection	Visit site for random inspections if considered warranted
Work record Profile	Annexure C245.A String Line		Voltagi - i restr di som		
Sprayed Bituminous Surfacing					
Material Quality	QA Material Supplier		Construction Specification C244	Engineer to undertake a	Visit site for random inspections if considered
Work Records	Spray Record Sheet Details of Work Form - Annexure C244.A	Construction Specifications C244.	Construction Specification C244	Pre-seal Inspection	warranted
Subsurface Drains Pipe Filter Material Cleaning Joints and Markers Geofabric	Visual QA Material Supplier Visual Visual	Construction Specifications C230, C231, C232, C233.	Each Each Each	Engineer to make random audit inspections of Contractors performance	Visit site for random inspections if considered warranted
Kerb and Channel Material Quality Horizontal & Vertical Alignments	Survey QA Material Supplier Water Test	Construction Specifications C224, C271.	Each 20m	Engineer to inspect prior to kerb placement and completed kerb. Water test where appropriate.	Visit site for random inspection if considered warranted.
Road Crossing Conduits Location Markers	Visual Visual		Each Conduit Each Marker	Engineer to make random Audit inspections of Contractors Performance	Visit site for random inspection is considered warranted

[#] Note: 50% of all core samples are to be taken 1m from the carriageway centreline

^{*} Note 1: All references relate to the Capricorn Municipal Development Guidelines

Council Reference No:	
-----------------------	--

DEVELOPMENT NAME:		Consulting Engineer:	
SEVELO: MEITH TO MILE.	***************************************	Contouring Engineer.	

Elements of Work	Testing Requirements		Consulting Engineer's Responsibility	Council's Responsibility	
	Test	Standard *(Refer Note 1)	Frequency		
Stormwater Drainage					
Location of Structures	Survey]	Each		Visit site for inspection prior to backfilling.
SL & IL at Structures	Survey	Construction Specification C220, C221, C222, C223.	Each	Engineer to make	
Material Quality/ Bedding,	Visual	J	Construction Specification C220, C221, C222, C223.	sufficient visits to asses compliance with specification & to view	
Manholes	Visual	Straightness	Each	progress and works	
Drain lines	Visual	Straightness	Each		
Backfilling	Visual	Construction Specification C220	Construction Specification C220		
CCTV Testing	CCTV		If ordered by Council#		
Topsoiling & Grassing	Visual	Construction Specification C273	Construction Specification C273	Engineer to confirm all affected areas are topsoiled, grassed & maintained.	Visit site for check at defects liability inspection.
Soil and Water Management Measures	Visual	Council approved Soil and Water Management Plan Contractor's Soil and Water Quality Management Strategy	Every site visit	Ensure continuous maintenance of measures	Ensure compliance with Council's local laws, Development guidelines and EPA requirements.
All Works Prior to Defects Liability	Visual		Inspections	Engineer to confirm all works comply with design intent before arranging "Defects Liability" inspection and complete the "Defects Liability" Inspection Checklist prior to joint inspection with Council	Joint "Defects Liability" inspection with Consulting Engineer & notify requirements, if any

^{*} Note 1: All references relate to the Capricorn Municipal Development Guidelines

Council Reference No:	
-----------------------	--

EXAMPLE SUBDIVISIONAL INSPECTION & TEST PLAN

DEVELOPMENT NAME: Consulting Engineer:

Elements of Work	Testing Requirements			Consulting Engineer's Responsibility	Council's Responsibility
	Test	Standard *(Refer Note 1)	Frequency		
Sewerage Reticulation					Witness hydrostatic testing
Location MH's & HC's	Survey		Each		of manholes
IL at MH & HC's	Survey		Each	Engineer to make random	Visual inspection of lines
Bedding	Visual		Construction Specification C402	visits to confirm generally that all structures &	prior to backfill if CCTV inspection of lines is not
Manholes & Benching	Appearance-structural integrity		Each	pipelines are constructed & located within Council	ordered
Pipelines	Survey	Construction Specification	Each	tolerances and to assess all test results. Engineer	Witness air pressure test.
Backfilling> 2m deep and a road crossing	Compaction AS1289	C402	Construction Specification C402	to witness & approve all pressure tests of the lines,	Audit inspections to mirror some lines only. Joint "Defects Liability"
Pressure Testing Pipelines	Air Pressure Test		All lines	all hydrostatic tests at all manholes and mirror all	inspection with Consulting
Hydrostatic Testing of Manholes	Hydrostatic Testing		Each Manhole	lines	Engineer & notify requirements, if any.
CCTV Testing	CCTV)	If ordered by Council #		

[#] Note: Prior to backfill inspections not required if CCTV ordered

^{*} Note 1: All references relate to the Capricorn Municipal Development Guidelines

Council Reference No:	
-----------------------	--

DEVELOPMENT NAME: Consulting Engineer:	
--	--

Elements of Work	Testing Requirements		Consulting Engineer's Responsibility	Council's Responsibility	
	Test	Standard *(Refer Note 1)	Frequency		
Water Reticulation					
Location					
RP Boundary Set Out	Survey		All lines		
Valves, Hydrants, Scours,	Visual			Engineer to make	Witness Water pressure
Bends	- Surface Boxes		Each	sufficient job visits to	tests.
	- Other		All lines	confirm generally that construction is in	Joint "Defects Liability"
Depth	Reduced Level (where nominated) Visual elsewhere	Construction Specification C401	Construction Specification C401	accordance with requirements & that location of all fittings are	inspection with Consulting Engineer & notify requirements, if any. Visual site inspection prior to backfill and line
Material Quality (Bedding, Concrete, Pipes)	QA Material Supplier		J	within Council Tolerances. Pressure testing of all	
Pipelines	Visual		Each	pipelines to be witnessed.	sterilisation.
Backfilling	AS1289		Construction Specification C401		
Pressure Testing	Pressure Test	/	All lines		
Disinfection	Chlorine residual		Construction Specification C401		
Minor Concrete Works/ Ready Mix				Engineer to make	
Material Quality	QA Material Supplier			sufficient visits to asses	Visit site for random
Consistency	Slump Test		1 per Load (Max Lot size 15m³)	compliance with specification & to view	inspection if considered warranted.
Strength	Compressive Strength		2 pairs per 15m ³	progress and works	Traina no an
Finished Surface	Visual		1 cross-section per 15m		
Minor Concrete Works/ Sprayed Concrete	OA Matarial O analian	Construction Specification		Engineer to make sufficient visits to asses	Visit site for random
Material Quality Strength	QA Material Supplier Test Panels and Cores and Compressive Strength Cores	J	Construction Specification C271	compliance with specification & to view progress and works	inspection if considered warranted.

^{*} Note 1: All references relate to the Capricorn Municipal Development Guidelines

Council Reference No: .	
-------------------------	--

DEVELOPIVIENT NAIVIE	DEVELOPMENT NAME:		Consulting Engineer:	
----------------------	-------------------	--	----------------------	--

Elements of Work	Testing Requirements		Consulting Engineer's Responsibility	Council's Responsibility	
	Test	Standard *(Refer Note 1)	Frequency		
Prior to Acceptance of works for "Defects Liability Period"	As constructed Drawings to be prepared and Submitted to Council All Test results to be compiled and held by Consulting Engineer and a confirmation statement of this shall be forwarded to Council with request for "Defects Liability".			Forward "As Constructed" submission to Council. Ensure Registered Surveyor (QLD) certificate is attached and also attached Engineers certification. Finalise all other Documentation in accordance with CMDG Construction Procedures.	Council to accept & conduct Audit checks of As Constructed Drawings & advise any requirements. When completed advise in writing of acceptance of works for commencement of "Defects Liability Period"
During "Defects Liability Period"	Any defects to be repaired Works to be maintained as per Specification		Consulting Engineer to confirm all minor omissions & defects have received suitable attention & to examine & approve site prior or asking for "Final Acceptance of works" Inspection	Council to advise Consulting Engineer of any defects	
Prior to Final Acceptance of works.	Confirmation that no defects are evident Works maintained safe & in good order All Test results to be compiled (for example CCTV if required) and held by Consulting Engineer and a confirmation statement of this shall be forwarded to Council with request for "Off Defects Liability".		Consulting Engineer to accompany Council Inspector & to note any requirements and forward test results if required.	Council Inspector to accompany Consulting Engineer & Contractor & to advise any requirements. When completed advise in writing of final acceptance of works.	

^{*} Note 1: All references relate to the Capricorn Municipal Development Guidelines